KOLAR DIVISION.

Dated 11th May 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 30th May 1911, for restoring Kuppam Tank, Registered No. 703, Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kuppam Tank, Registered No. 703, Bowringpet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Tenders which are not accompanied by schedule of rates are likely to be rejected.

Items	Per	Bund	Left weir	Right weir	Constructing lifting dam and channel	Constructing tunnel at the end of flank board
		Quantity	Quantity	Quantity	Quantity	Quantity
Earthwork with consolidation	C. yd.	8740	...	...	...	...
Turfing	S. yd.	9209	...	...	...	...
Removing and refixing old grade stones, Registered No. and date stones	No.	34	...	...	...	...
Removing and resetting old stone work with new jelly	C. yd.	2063	...	...	...	...
New stone work	,,	2107	...	...	...	...
Gravel backing	,,	865	...	...	...	...
Cutting and removing high ground, hard gravelly soil mixed with soft rock.	,,	...	196	...	...	...
Blasting rock	,,	...	...	58	...	2
Burnt brick in surki mortar	C. ft.	...	120	417	...	...
Earthwork, opening a new channel, blasting hard rock	C. yd.	...	...	...	67½	...
Surki plastering	Sqr.	...	3·00	5·00	...	...
Burnt stone old slabs with resetting with brick in chunam top and relaying.	S. ft.	...	241	216	...	...
Burnt stone slabs, new, with dressing	,,	...	...	247	294	35
Earthwork, opening a channel, cutting soft rock	C. yd.	...	...	...	67½	...
Repairing washed-out apron with two-third new stone	,,	...	...	132	...	...
Earthwork, excavation, hard chettu soil	,,	...	...	...	49	...
Burnt stone in surki mortar	C. ft.	...	...	...	2066	120
Pointing with do	Sqr.	...	...	...	8·00	...
Grooving gibbet stones of head sluice, 3"	R. ft.	...	...	...	15	...
Cutting holes in slabs	,,	...	...	...	4	...
Teakwood work for fixing gear rod with nuts	C. ft.	...	...	...	2	...
Gibbet stones of head sluice grooved 3" at side 9" thick	,,	...	...	...	8½	...
Shutter of head sluice 2'×3' with gear rod, etc.	,,	...	Lump sum Rs.			
Clearing jungle	,,	...	Lump sum Rs.			
Earthwork, cutting bund for constructing tunnel and refilling.	C. yd.	...	...	...	...	57
Repairing the weirs to existing portions wherever necessary.	,,		Lump sum Rs.			
Repairing the existing relieving weir and joining it with the new wall.	,,		Lump sum Rs.			

B. B. GARUDACHARYA,
Executive Engineer.